

START HERE — Advisor Review

Dry Lightning 3000 Kickstarter package, draft v1 (2026-09-17)

Status: DRAFT WITH LAUNCH BLOCKERS. Not approved, not ready to launch, nothing published or sent.

Prepared for Jeremy Coon and his business advisor from the Wildfire Watchdog Drive records, the accessible mailbox, and public research. Everything is editable. Where I made a routine decision, it is logged in `10_registers/DECISION_LOG.md` and can be reversed.

1. One-page summary

Product. Dry Lightning 3000 v1: a Honda iGX390 electric-start high-pressure water pump on a steel skid, controlled by a four-button rolling-code key fob (crank, run/stop, throttle, discharge valve) through relays wired so that losing power or signal kills the engine, idles the throttle and closes the valve. Manual switches work with nothing plugged in. No app, no internet, no sensors, no sprinklers. The phone/dashboard prototype is described honestly as demonstrated but not for sale in v1.

Audience (recommended). Rural and wildland-urban-interface homeowners and small ranch/camp operators in the western US who already have a water source (tank, pond, pool) and are buying equipment in the October–March planning season. One primary audience; institutional buyers are a secondary, unpaid outreach track.

Positioning. "The pump you don't have to stand next to." Between a \$1,200 NorthStar pump plus a \$300 start/stop remote (no throttle, no valve) and a \$20,000+ installed sprinkler system. Sell remote operation and failsafe engineering, never protection guarantees (Kickstarter's prohibited-items rule bars injury/death-prevention claims).

Funding goal. \$60,000 all-or-nothing, derived from a 10-pump minimum batch plus one-time costs (insurance, FCC declaration, testing, tooling) and 10% contingency.

Rewards. Supporter \$35 · Remote Control Kit \$1,250 (limit 10) · DL3000 Early Bird \$4,699 (limit 10) · DL3000 \$4,999 (limit 15, equals the MAP proposed to Northern Tool) · DL3000 + Hose & Nozzle \$5,599 (limit 10). Freight \$349 flat, contiguous US only. Hard cap 35 pumps.

Timeline. Prelaunch page Dec 20, 2026 → launch Jan 19, 2027 → end Feb 18 → payout ~Mar 4 → kits ship April → Early Bird pumps June → remaining July 2027.

Money. Base case (18 pumps, 5 kits, 80 supporters): ~\$104k gross, ~\$93k net after fees and dropped pledges, ~\$85.5k cost to deliver including a full year of \$2M/\$4M insurance, ~\$7.5k surplus before tax. Founder cash needed before payout: ~\$8,000 (video, tooling, half the insurance down payment, optional ads). Conservative case (8 pumps) does not reach the goal, so nothing is charged and nothing is owed.

2. Every deliverable (all in kickstarter - campaign/ on the GitHub branch and in the Drive folder "Kickstarter Campaign")

Deliverable	File	State
This document (+ PDF)	<code>00_START_HERE/START_HERE_Advisor_Review.md, .pdf</code>	Complete
Research: technical evidence	<code>01_research/technical_evidence.md</code>	Complete (some folders skimmed; noted in file)
Research: costs, insurance, patent, Northern Tool	<code>01_research/costs_insurance_legal.md</code>	Complete

Deliverable	File	State
Research: founder and history	01_research/founder_and_history.md	Complete
Research: Kickstarter rules and competitors	01_research/kickstarter_rules_and_competitors.md	Complete (rule text from search extracts; re-verify in editor)
Research: media inventory	01_research/media_inventory.md	Complete
Scope and claims register	02_campaign_copy/01_scope_and_claims.md	Complete
Master campaign copy (title → FAQ → disclosures)	02_campaign_copy/MASTER_CAMPAIGN.md	Complete draft, [REVIEW] notes inside
Financial workbook (live formulas, 3 scenarios, stress tests, cash timing)	03_financial_model/WW_Kickstarter_Financial_Model_v1.xlsx (+ build_workbook.py)	Complete, recalculated, 0 formula errors
Reward structure	04_rewards_and_fulfillment/REWARD_STRUCTURE.md	Complete
Manufacturing & fulfillment plan, BOM	04_rewards_and_fulfillment/MANUFACTURING_FULFILLMENT_PLAN.md	Complete (no supplier quotes yet)
Supplier RFQs (unsent)	04_rewards_and_fulfillment/SUPPLIER_RFQ_DRAFTS_UNSENT.md	Complete, unsent
Warranty and backer terms	04_rewards_and_fulfillment/WARRANTY_AND_TERMS_DRAFT.md	Draft, attorney review recommended
Graphics: use of funds, timeline, system diagram, feature panels, reward cards, status panel, cover template	05_media/*.png (+ build_graphics.py)	Complete; cover needs the real photo
Real photos pulled from Drive	05_media/photos/ (+ DRIVE_SOURCES.md)	10 files; hero set NOT obtained (see blockers)
Video script, storyboard, shot list, EN/ES captions	06_video/VIDEO_SCRIPT_AND_STORYBOARD.md	Complete; no edited video (footage not transferable, key shots missing)
Marketing: 30-day prelaunch, calendar, 7 emails, 10 posts, 5 ads, press release, pitch, templates, EN+ES	07_marketing/MARKETING_PACKAGE.md	Complete, unsent
Private preview page (mobile-tested)	08_preview_site/index.html (+ preview_mobile.png)	Complete
Prelaunch landing page + signup workflow (test mode)	08_preview_site/prelaunch_landing.html, SIGNUP_WORKFLOW.md	Complete, inactive
Kickstarter field-by-field upload package	09_upload_package/KICKSTARTER_UPLOAD_PACKAGE.md	Complete; no draft populated (no account access)
Source/assumption register, decision log, change log, task register, verification log	10_registers/	Complete
Downloadable package	WW_Kickstarter_Campaign_v1.zip (Drive + GitHub)	Complete

Private preview: open 08_preview_site/index.html from the zip or the Drive folder in any browser (works offline; phone-width tested, no horizontal scroll).

3. Major recommendations and why

- 1. Fund v1 as the fob pump only; keep phone control as a disclosed development goal.** The insurance being placed, the FCC path and the briefing all define v1 this way. Promising app control would put the campaign outside the policy scope and add a \$8k–\$200k certification path.
- 2. Goal \$60,000, not \$130,000.** The business plan's \$130k covers a 50-unit inventory run for retail. Kickstarter should fund only what backers actually order plus fixed costs; a lower goal is more likely to fund and still covers insurance.

3. **Price at or above the Northern Tool MAP (\$4,999) except ten Early Birds.** Protects a future retail relationship and keeps ~\$1,875 contribution per pump after fees, parts and freight.
4. **Launch January 19, 2027, 30 days.** Inside the planning season the advisor described, after the holidays, leaves time for a real demo video and supplier quotes, and lands payout before spring builds. Northern Tool listing (target March 1) is not affected.
5. **Order nothing before payout.** Keeps founder cash exposure near \$8,000. Honda engines are stocked; the 3-week lead time fits the delivery windows.
6. **US-48 only, freight shown separately at \$349.** The crate is 165 lb; international adds regulatory and cost risk for a first batch.
7. **No sprinkler or "whole-house" tiers, no stretch goals.** They change the insurance class and the delivery promise.
8. **Unpaid outreach first, \$1,500 optional Meta test with a stop rule.** No ad results exist for Wildfire Watchdog; do not make ads a hidden requirement.
9. **Answer Kickstarter's AI questions truthfully:** text drafted with AI help from Jeremy's records; no AI images of the product.
10. **Bind StarStone (\$2M/\$4M) if Northern Tool proceeds; otherwise Kinsale (\$1M/\$2M) saves \$6,000.** The model's base case carries the expensive one so the goal is safe either way. Correct the application wording to the v1 product description first.

4. Assumptions, evidence gaps, genuine blockers

Launch blockers (must be cleared before submitting to Kickstarter):

1. **The fob-controlled control box does not exist yet.** The 2026-09-10 briefing is a design and parts list; what runs today is the prototype's ESP wireless link (remote crank/kill confirmed working, phone/dashboard start bench-proven 2026-08-23) and the local toggle. Kickstarter requires the prototype to perform every advertised function on camera, so the fob box must be built (about \$200 in parts, a few days of shop time), tested with the failsafe stopwatch, and filmed before submission. This is the single biggest blocker and the first item on the owner list.
2. **Measured numbers.** Flow, pressure, range and failsafe timing have never been measured. The copy says "specified" and "measured before shipping"; the video needs at least one real reading.
3. **Identity, LLC, EIN, bank and Stripe verification** on Kickstarter. Owner only.
4. **Insurance binding plan.** Not a Kickstarter rule, but no pump should ship uninsured. Quotes exist; nothing is bound; the Kinsale application wording must be corrected to the v1 description.
5. **Real photographs of the prototype** in the package (they exist on wildfirewatchdog.com; originals were not reachable from this session).

Evidence gaps (weaken the plan, do not block): no supplier quotes for engine, pump end, frame, valve, receivers, FCC lab or freight (RFQs drafted); no DL3000 customers or testimonials; founder background claim ("firefighting, irrigation") unconfirmed; business mailbox not read directly; the Field Unit 001 trailer build has no completion evidence.

Key assumptions: per-unit cost \$2,665 at 10 units (bottom-up; the business plan's \$1,700 is for 50 units on a cheaper engine); 3% dropped pledges; 6 hours per pump; \$380 freight cost; StarStone premium in the base case.

5. Decisions for Jeremy and the advisor (recommended answer first)

#	Decision	Recommended	Alternative
1	Run a Kickstarter at all, versus direct presales on wildfirewatchdog.com	Yes, Kickstarter for all-or-nothing protection, deadline, and a public demand signal usable with Northern Tool and lenders	Direct presales with Stripe (no fees on failure, less reach, no deadline)
2	Goal	\$60,000	\$65,000 (safer if only Early Birds sell) or \$50,000 (8 pumps, thinner)
3	Engine for the batch	Honda iGX390 (prototype engine)	NorthStar e420 once bench-tested and quoted
4	Insurance carrier	StarStone \$2M/\$4M if NTE proceeds; Kinsale otherwise	—
5	Prices/caps	As proposed (\$4,699 ×10 / \$4,999 ×15 / \$5,599 ×10)	Drop Early Bird to \$4,499 if prelaunch list is weak
6	Offer the \$1,250 Remote Control Kit tier	Yes, capped at 10 , Honda iGX390 only	Skip it to simplify support
7	Include the spring-return valve in the base package	Yes	Make it a \$250 add-on (lowers base cost, hurts the "four buttons" story)
8	Launch date	Jan 19, 2027	Feb 2 if video/quotes slip
9	Paid ads	\$0 required; \$1,500 optional test	None
10	Bend pickup option	Yes, refunds freight	No
11	Attorney review of warranty/terms	Yes, ~\$900	Self-review
12	Tell Northern Tool about the campaign beforehand	Yes, courtesy note, pricing at MAP	Do not mention

6. Remaining owner-only actions

1. Build the fob control box per the 2026-09-10 briefing (include the starter-isolation relay learned from the 2026-08-02 backfeed fault), then film the shot list in 06_video/ (fob sequence, failsafe with stopwatch, wet test with gauge, range test).
2. Upload the hero photo set (PXL_20260817 series) and the three demo videos into the Drive "Kickstarter Campaign/media" folder.
3. Confirm or rewrite the founder story in your own words; confirm the background claim or drop it.
4. Complete Kickstarter identity/bank/Stripe verification; create the project draft and paste from 09_upload_package/.
5. Approve and send the RFQs; replace model estimates with quotes.
6. Decide the insurance carrier; correct the application wording; plan to bind on campaign success.
7. USPTO: micro-entity certificate/surcharge due 2026-09-23; non-provisional by 2027-01-11 (not a campaign task, but the "patent pending" claim depends on it).
8. Approve the marketing package; nothing has been sent.
9. Copy this package to KVM 2 if you want it there (kickstarter-campaign/ on the GitHub branch; no VPS access existed in this session).

7. Launch and fulfillment checklist (after approval)

Pre-launch: quotes in → update Inputs sheet → re-check goal · video edited · real photos placed · [REVIEW] notes cleared · prelaunch page live (Dec 20) · email 1 sent · press release sent · Firewise/HOA notes sent · followers ≥ 300 and ≥ 10

committed pump backers · Late Pledges on · advisor sign-off.

Campaign: day-one push · reply to every comment within 4 h · updates on days 1, 2, 7, 14, 21, 28, 30 · live Q&A day 12 · supplier status update day 21.

Post-campaign: payout → orders same week → bind insurance → FCC lab booked → backer survey → build sheets per serial → wet-test certificates → freight booked → delivery emails with photos → 30-day check-in → warranty log.

Package built by Claude (Anthropic) as campaign producer on 2026-09-17 from the founder's records; all decisions here are recommendations for the founder and advisor.

Campaign Scope and Claims Register (DRAFT v1, 2026-09-17)

Purpose: the single place that says what this campaign delivers, what is demonstrated, what is still development, and which claims are allowed in public copy. Labels: VERIFIED (document, receipt, test or code on file), ESTIMATE (basis and range stated), PROPOSED (campaign decision awaiting approval), UNKNOWN (no evidence). Sources in 01_research/.

1. The product being funded

Dry Lightning 3000 (DL3000) v1: Honda iGX390 electric-start engine + high-pressure pump end on a steel skid, controlled by a four-button rolling-code RF key fob through two Solidremote 202U receivers and three relays (kill, throttle, valve), with a spring-return 2 in. discharge valve, manual override switches, 12 V battery/solar maintainer, and a documented 6-pin Remote Port. No app, no internet, no monitoring, no sensors, no sprinklers.

Basis: RF briefing 2026-09-10 (VERIFIED as the current design intent), product page 2026-09-11, Quick Start Guide 2026-09-12, business plan 2026-09-15.

2. What still needs development before delivery

Item	Status	Evidence
Fob control box (Solidremote receivers + relays) built and tested on the actual pump	NOT BUILT — design and parts list only (briefing 2026-09-10); demo video shows the ESP/dashboard path; a 2026-08-02 field fault (starter cranked from battery backfeed) was fixed in the ESP path with an isolation relay and must be designed into the RF box too	briefing 2026-09-10; NT status 2026-08-29
Spring-return (fail-closed) valve actuator	IN DEVELOPMENT — prototype uses a motorized CR04 valve without spring return	sourcing sheet 2026-07-05; briefing parts list
Failsafe timing test (≤ 2 s)	NOT YET MEASURED	briefing §2 "required failsafe behavior"
Flow / pressure / range measurements	NOT YET MEASURED (product page: "specifications are preliminary")	product page 2026-09-11
Pump end supplier and sample test	UNKNOWN — RFQ targets identified, no quote	Master_Parts_Categories 2026-07-02
FCC Supplier's Declaration of Conformity for the control box	NOT STARTED (budgeted)	briefing §5
Product-liability insurance	QUOTED, NOT BOUND (Kinsale \$4,598 / StarStone \$10,598)	quote 2026-09-01; plan 2026-09-15
Warranty and terms of sale	DRAFTED in this package; attorney review recommended	plan §8
Engine choice (Honda iGX390 vs NorthStar e420)	DECIDED FOR THIS CAMPAIGN: Honda iGX390 (the prototype engine and the one on both Northern Tool packets); e420 remains an option for later retail runs	conflict noted in costs research §7

3. Role of each component in v1

Component	Role	In reward?
Pump (engine + pump end)	Moves water; the product	Yes
Local remote (RF fob)	Only control link: crank, run/stop, throttle, valve	Yes
Manual switches	Backup control with nothing plugged in	Yes

Component	Role	In reward?
Phone control / dashboard	Prototype only; future development; depends on power, connectivity, water and hoses in place	No (described honestly)
Sensors / auto-start	Prototype/patent-application concept; not v1	No
Valve	2 in. spring-return discharge valve, opened by button D, closes on stop/power loss	Yes
Hoses, nozzle, strainer	Required to use the pump; optional package	Only in Tier 5 / add-on
Sprinklers	Customer-supplied; not sold in this campaign	No
Water source, fuel, operator	Customer-supplied dependencies	No

4. Feature status matrix (public copy must match)

Feature	Status	Say in copy
Remote engine start (timed crank)	DEMONSTRATED on prototype via ESP link (README 2026-08-08 'confirmed working'); fob path DESIGNED, not built	"Demonstrated on the prototype"
Remote stop/kill	DEMONSTRATED	same
Remote throttle idle/full	IN DEVELOPMENT (ESP throttle receiver built; polarity test pending per 2026-08-05 wire map; fob channel designed)	same
Remote discharge valve	IN DEVELOPMENT (motorized valve receiver exists; spring-return actuator not fitted)	"Spring-return actuator is the production part"
Interlock (C/D dead unless RUN)	DESIGNED (wiring spec)	"wired so that..."; measure before launch video
Failsafe on signal/power loss	DESIGNED; ESP version had heartbeat failsafe in firmware	"Design target within 2 s; measured on every unit"
Manual override	DESIGNED (in spec and product page)	"Manual controls remain available"
One-shot starter protection, max-run shutdown	Listed on product page (ESP firmware features)	Only claim if present in fob v1 wiring; otherwise omit [REVIEW]
Phone/cloud start	DEMONSTRATED 2026-08-23 (prototype)	"Prototype only, not in v1"
Auto-start on sensor	CONCEPT / patent application	Do not claim
Low-water shutdown, drain valve, sprinklers, solar system	Other product lines / prototypes	Do not claim for DL3000
150 GPM / 140 PSI	CLAIMED class spec, unmeasured	"specified ... class"; publish measured
~10 h on 10 gal	ESTIMATE, unmeasured	"design estimate" or omit
~150 ft range	Receiver-maker spec, unmeasured	"as specified; measured before shipping"
Patent pending	VERIFIED for the automatic system (2 provisionals, 2026-01-11); NOT the fob v1	"Patent pending on the automatic version; v1 fob not its subject"
"Only remote-start pump" / "only in category"	UNSUPPORTED (competitors listed in the founder's own briefing and research §4)	Never
Northern Tool	Onboarding in progress; no PO, listing or commitment	Do not mention as partner/endorsement; courtesy notice only
Customers / testimonials	One completed install (Metolius River, May 2026), sprinkler system not DL3000; no DL3000 customers	Only "a three-building system I installed"; no testimonials
Test results	None recorded for DL3000	Never invent; promise per-unit certificate

5. Claims policy for all public copy

Never: "only," "guaranteed," "saves lives," "prevents injury or death," "protects your home," "fireproof," "patented," "encrypted," "partnered with Northern Tool," any statistic without a cited source, any customer quote not on file, any AI image of the product.

Always: the standard disclaimer; "preparedness equipment"; "operator present"; "requires water source, fuel, hoses"; "estimated delivery"; "patent pending (provisional)".

6. Insurance scope check

The Kinsale application wording ("Fire Suppression Systems – installation, servicing or repair"; "Installation Contractor") does not match the v1 product description the briefing requires for both carriers ("gas engine powered wildfire water pump with RF key-fob remote... no app, no internet, no monitoring"). Before binding, the application must be corrected to the v1 description, and the campaign copy must stay inside it: no sprinklers, no monitoring, no installation, no app. This package complies.

7. Decisions made in this draft (for approval)

1. Honda iGX390 is the campaign engine.
2. Spring-return valve is included in the base package (not an upgrade).
3. Phone control is described as a demonstrated prototype and future development, not a reward or stretch goal.
4. Sprinklers excluded; hoses/nozzle only as Tier 5 and add-ons.
5. Shipping contiguous US only; no international.
6. Goal \$60,000; 30 days; launch 2027-01-19.

MASTER CAMPAIGN — Dry Lightning 3000 on Kickstarter

DRAFT v1 for advisor review, 2026-09-17. Nothing here is published. Bracketed [REVIEW] notes are for Jeremy and the advisor and must be removed before upload. Every claim traces to 01_research/ or to the feature matrix in 01_scope_and_claims.md.

A. Basics (Kickstarter "Basics" tab)

Project title (60 chars max):

Dry Lightning 3000: Remote-Start Wildfire Water Pump

[47 characters]

Subtitle / blurb (135 chars max):

A Honda-powered high-pressure pump you start, throttle and open from a key fob, so nobody stands next to it in the smoke. Built in Oregon.

[135 characters — verify count in the editor]

Category: Technology › Hardware

Reason: Kickstarter's hardware rules (working prototype, no renders) apply anyway, and hardware backers expect engineering detail. Design › Product Design is the alternative.

Location: Bend, Oregon

Campaign length: 30 days. Proposed launch Tuesday 2027-01-19, end Thursday 2027-02-18.

Funding goal: \$60,000 (derived on the Funding_Goal sheet: 10 pumps plus insurance, FCC declaration, testing, tooling and contingency).

Short pitch (for prelaunch page and social, ≤ 300 chars):

Wildfire season is not the time to walk into embers to yank a pull-cord. The Dry Lightning 3000 is a Honda iGX390 high-pressure water pump with a four-button rolling-code remote: start, throttle, open the discharge valve, and stop, from up to about 150 feet away. No app, no internet, no subscription. Built and wet-tested in Bend, Oregon.

B. Campaign video

See 06_video/VIDEO_SCRIPT_AND_STORYBOARD.md. Real footage only; the fob start, throttle, valve and stop must be shown on the actual unit.

C. Project description (the long page)

1. The one-sentence version

The Dry Lightning 3000 is a gas-engine high-pressure water pump you can start, run up to full throttle, open the water valve on, and shut down from a handheld remote, so you can wet down your home, barn or defensible space without standing at the pump.

2. Why I built this

[REVIEW: Jeremy must confirm or rewrite this section in his own voice. The records contain no first-person origin story; the facts below are all that is documented. Do not add a personal fire-loss story unless it is true.]

I'm Jeremy Coon. I live and work in Bend, Oregon, in the middle of the country's wildland-urban interface. For the past two years I have been building remote-control systems for water pumps in my shop: first wireless sprinkler controllers in a toolbox, then a fixed three-building system I installed on the Metolius River in spring 2026, and then the question that turned into this product.

Every gas fire pump on the market assumes somebody is standing next to it. In a real fire, that somebody has evacuated, is asleep, or does not want to walk toward the embers to pull a rope. I wanted a pump I could start from the truck, the porch, or the end of the driveway, and shut down the same way.

So I designed the control system around a commercial Honda engine: relays that turn the ignition, starter, throttle and a powered discharge valve into four buttons on a rolling-code key fob, wired so that if the remote link or the power ever drops, the engine kills, the throttle returns to idle and the valve closes on its own. I built the prototype, filed two provisional patent applications on the automatic version in January 2026, and by August 2026 had the unit you see in these photos starting and stopping wirelessly from my phone and from a bench switch. The key-fob control box is the production design of that same relay system; building and testing it on this pump is the first job this campaign funds, and it will be on video before launch.

This campaign funds the first production batch of the fob-controlled version, built and tested in Bend.

3. The problem, plainly

- Insurers in wildfire areas are non-renewing policies and pricing mitigation into rates. (Background sources, not statistics we claim: California Department of Insurance 2026 briefing; Oregon Division of Financial Regulation 2026 emergency order on non-renewals; reporting on Deschutes County FAIR Plan growth. See 01_research/kickstarter_rules_and_competitors.md §6.)
- Installed exterior sprinkler systems cost in the tens of thousands of dollars and take a contractor.
- A good portable pump costs a thousand to two thousand dollars and needs a person at the pull-cord, the choke and the valve.
- Add-on engine remote-start kits exist, but they are start/stop only. They do not run the throttle up, and they do not open a water valve.

4. What the Dry Lightning 3000 does

Button	What happens	Status (2026-09-17)
A — Crank	Starter engages for a timed pulse	Remote crank demonstrated on the prototype (wireless ESP link); fob receiver wiring designed, to be built and filmed before launch
B — Run / Stop	Ignition enabled; press again to stop	Remote run/kill demonstrated on the prototype; fob path as above
C — Throttle	Idle ↔ full throttle	Throttle receiver built in the prototype; final polarity test pending; fob path as above
D — Valve	2 in. discharge valve closed ↔ open	Motorized valve controlled in the prototype; spring-return failsafe actuator is the production part, not yet fitted

[REVIEW: Kickstarter requires the prototype to perform every advertised function on camera. The fob-controlled build must exist and be filmed before this page is submitted. Until then this section is a development statement, not a demonstration claim.]

Safety interlock: buttons C and D are physically dead unless the engine is enabled to run. Press B to stop and both the throttle and the valve drop to their safe default automatically. Loss of power or remote signal does the same. Manual

switches on the pump work with nothing plugged in.

Range: rolling-code RF, roughly 150 ft line of sight [REVIEW: not yet measured on the production receivers; publish the measured figure from the range test or say "measured before shipping"].

5. What you get

The Dry Lightning 3000 v1 base package:

- Honda iGX390 electric-start engine, 389 cc, on a powder-coated steel skid with lifting points
- Matched high-pressure pump end, 2 in. suction and discharge
- Four-channel rolling-code remote system with one fob in use and three spare fobs
- Sealed relay control box with failsafe wiring and manual override switches
- 2 in. 12 V spring-return electric discharge valve and 2 in. camlock fitting
- 12 V battery, USB power bank and solar maintainer panel
- Documented 6-pin Remote Port for future controllers
- Quick Start Guide, warning labels, and a wet-test certificate with your unit's measured flow and pressure
- 12-month limited warranty and direct support from the builder

Not included: fuel, hoses, nozzle, strainer (available in the Hose & Nozzle Package), sprinklers, a water source, or installation.

6. Performance

The pump end is specified in the 150 GPM / 140 PSI class at the iGX390's 3,600 rpm. [REVIEW: these are catalog-class figures, not measured on the prototype. Kickstarter copy must say "specified" and promise the measured wet-test numbers on each unit's certificate.] Fuel: ~10 hours on a 10-gallon auxiliary tank at full throttle is the design estimate [REVIEW: ESTIMATE, unmeasured; state as estimate or omit]. Every unit is wet-tested before it ships, and you receive its measured numbers.

7. How it fits into your property

A pump is only one part of watering a property. You supply the water (pond, tank, pool, cistern, irrigation line), the suction and discharge hoses, and the nozzle or sprinklers. The DL3000 moves the water and lets you control the engine and valve from a distance. Typical uses: wetting roofs, decks and defensible space ahead of an approaching fire, filling tanks, feeding existing sprinkler lines, and general high-pressure water transfer on ranches and camps.

8. What this campaign does NOT promise

- It is not a monitoring, alarm or fire-detection device. It does not start itself.
- It does not connect to the internet or a phone in v1.
- It does not include sprinklers or installation.
- It does not make property fireproof, does not guarantee protection, and does not replace defensible space, firefighters or evacuation orders. If you are told to evacuate, evacuate.
- It is preparedness equipment. It requires an operator present to supervise it, a water source, fuel and hoses.

9. Phone control: where it really stands

The prototype has a second control path: an ESP-based wireless link to a self-hosted dashboard that I have used to start and stop the pump from my phone (first end-to-end cloud start on 2026-08-23; a short demo was recorded). It works in my

shop. It is not in the v1 reward because:

1. A custom radio design needs its own FCC certification, which costs far more than the declaration path used for the pre-certified fob receivers.
2. The product-liability insurance being placed for v1 is scoped to a locally-operated pump with no app, internet or monitoring.
3. Phone control depends on a power source, a connectivity path at the pump, and water and hoses being already in place, and I am not going to sell "start it from anywhere" until the failure modes are engineered and tested.

Every DL3000 ships with the documented Remote Port so a future connected controller can plug in without rewiring. If this campaign funds, part of the surplus goes to that development. It is a development goal, not a stretch reward.

10. What this campaign funds (use of funds)

Based on the financial workbook, at the \$60,000 goal:

- Parts and assembly of the first 10 pumps: ~51%
- Product-liability insurance (year one): ~18%
- FCC Supplier's Declaration of Conformity testing and documentation: ~4%
- Flow/pressure/failsafe validation and test gear: ~3%
- Assembly fixtures, tooling, crates: ~2%
- Kickstarter and payment fees, dropped pledges: ~11%
- Contingency: ~8%
- Video, legal review, software: ~3%

[REVIEW: percentages generated from Funding_Goal sheet; recalculate if the goal changes. Use-of-funds graphic in 05_media.]

11. Production plan and timeline

When	What
Feb 18, 2027	Campaign ends
Early March	Funds arrive; engines, pump ends, frames and valves ordered; insurance bound; FCC testing booked
Late March	Parts in; harness sub-assemblies built in batches
April	Remote Control Kits and Supporter rewards ship; first pumps assembled
May	Early Bird pumps wet-tested, crated and shipped
June–July	Remaining pumps shipped; final update

Every unit: bench test of the relay logic, failsafe timing test (kill, idle, valve-close within 2 seconds of losing the RUN signal), 20–30 minute wet test with measured flow and pressure, range test, then crate.

12. Shipping

Contiguous United States only. Pumps ship drained and without fuel, crated on a pallet (about 165 lb packed), by LTL freight with liftgate to a residential address. Freight is charged as a flat \$349 with your pledge. Local pickup in Bend, Oregon, refunds the freight charge [REVIEW: confirm you want to offer pickup]. Alaska, Hawaii, Canada and international: not in this campaign.

13. Support and warranty

Phone and email support from the person who built your pump. 12-month limited warranty on the frame, harness, control box, remote system, valve and pump end; the Honda engine carries Honda's own warranty through Honda dealers. Full draft terms are in the FAQ. Fuel, oil and filters are yours; there are no subscriptions.

14. Why crowdfunding

I am one person building this in Bend. A retailer conversation is under way, but a first batch of pumps needs engines, pump ends and insurance paid for up front, and I would rather build ten pumps for people who want them now than borrow against inventory nobody has ordered. Kickstarter's all-or-nothing model also protects you: if the goal is not met, nobody is charged and nothing is owed.

15. Risks and challenges (required section)

- **Supply.** The Honda iGX390 is stocked by US distributors, but pump ends, spring-return valve actuators and steel frames are small-batch purchases. I have identified suppliers but do not yet hold quotes; the goal includes a 10% contingency and the delivery windows include a one-month buffer.
- **Regulatory.** The remote uses pre-certified FCC modules; the assembled control box still needs a Supplier's Declaration of Conformity test, budgeted and scheduled for March. There is no UL listing for this product class and none is claimed. The Honda engine carries its own EPA/CARB emissions certification; California backers should confirm current CARB rules for their use.
- **Patent.** Two provisional applications are on file for the automatic version of the system. Provisional means "patent pending," not granted, and the fob-controlled v1 is not itself the subject of those filings.
- **Performance claims.** Flow and pressure are catalog-class figures until each unit is wet-tested; you get the measured numbers.
- **Capacity.** Founder-built, roughly four pumps a week. Reward quantities are capped at 35 pumps so the promise stays deliverable.
- **Insurance.** Product-liability coverage is quoted but not yet bound; it will be bound before any pump ships. If coverage terms require a design or wording change, backers will be told in an update.
- **Freight.** A 165 lb crate to a residence can be damaged or delayed; crates are built with corner posts and insured, and every unit is photographed before pickup.
- **Me.** One person can get sick or fall behind. Early Birds are built first; the kit and harness work is jig-based so a helper can step in.

16. Use of AI disclosure (required Kickstarter fields)

[REVIEW: answer truthfully in the editor. Proposed answers:]

- Does the project involve AI technology in the product? **No.** The DL3000 has no AI; it is relays and a rolling-code radio.
- Was AI used to create any content on the page? **Yes, in part.** The campaign text was drafted with AI assistance from the founder's own records, plans, firmware and test notes, then edited and approved by the founder. All product photographs and video are real footage of the actual prototype; no images or video of the product were generated or altered by AI. Explanatory diagrams are labeled as illustrations.
- Founder's own work, for the record: circuit design, harness, relay interlock and failsafe logic, firmware for the prototype's wireless version, dashboard, assembly and testing, patent drafting, and all product photography.

17. Closing

If you live where the fire maps keep changing, you already know the feeling of hoping the pump starts and hoping you never have to be the one standing next to it. Back the Dry Lightning 3000, and I will build yours, test it, send you its numbers, and

pick up the phone when you call.

Jeremy Coon, Wildfire Watchdog LLC, Bend, Oregon

Required disclaimer (appears on the page, on every pump reward and in the FAQ):

Preparedness equipment, not a guarantee. This product does not make property fireproof, guarantee protection, replace defensible space, or replace firefighters and evacuation procedures. It is not a monitoring, alarm or fire-detection device. Operate outdoors only, with an operator present, following the engine and pump instructions.

D. Rewards (Kickstarter "Rewards" tab) — copy per tier

Full logic in 04_rewards_and_fulfillment/REWARD_STRUCTURE.md.

\$35 — Supporter: Backer Wall + Decal (unlimited, ships March 2027, US)

Your name on the Founding Backers page (opt-in), a weatherproof Wildfire Watchdog decal, and every build update and test video.

\$1,250 — Remote Control Kit (Honda iGX390 retrofit) (limit 10, ships May 2027, US, +\$25 shipping)

The DL3000's four-channel rolling-code remote system for a pump you already own: two receivers, two fobs, sealed relay box with manual overrides, pre-terminated harness with 6-pin Remote Port, 2 in. 12 V spring-return discharge valve, installation guide and phone support. Compatible with Honda iGX390 electric-start engines with a 12 V battery. Requires basic 12 V wiring skill or a small-engine shop.

\$4,699 — Dry Lightning 3000: Early Bird (limit 10, ships June 2027, US, +\$349 freight)

The complete DL3000 v1 base package (see "What you get"), wet-tested with your unit's measured flow and pressure. Early Bird price for the first ten backers.

\$4,999 — Dry Lightning 3000: Kickstarter Price (limit 15, ships July 2027, US, +\$349 freight)

The complete DL3000 v1 base package at the Kickstarter price.

\$5,599 — Dry Lightning 3000 + Hose & Nozzle Package (limit 10, ships July 2027, US, +\$349 freight)

The complete DL3000 plus 50 ft of 2 in. discharge hose with camlocks, an adjustable fog/straight-stream nozzle, 20 ft of 2 in. suction hose with foot valve and strainer, and an extra fob. Add fuel and a water source and you are pumping.

Add-ons: extra paired fob \$45; second 50 ft 2 in. discharge hose \$220; extended warranty to 24 months \$350.

E. FAQ (22 questions)

- 1. Is this a sprinkler system?** No. It is a pump with remote engine and valve control. You connect your own hoses, nozzle or sprinkler lines.
- 2. Does it start by itself when it detects fire?** No. Version 1 starts only when you press the fob. Automatic and phone-triggered operation exist as a prototype and are a future development goal, not part of this reward.
- 3. How far does the remote work?** Rolling-code RF, roughly 150 ft line of sight as specified by the receiver maker. Each unit's range is measured before shipping and noted on its certificate.
- 4. What happens if the remote signal drops or the battery dies?** The control box is wired so that losing the RUN signal kills the ignition, returns the throttle to idle and closes the valve. Manual switches on the pump keep working.
- 5. Can someone else's remote start my pump?** The fob uses rolling codes that change every transmission, so a captured signal cannot be replayed. The receivers are paired to your fobs before shipping. (It is not AES-encrypted; we do not claim

"encrypted.")

6. **What water source do I need?** Any source the 2 in. suction hose can reach: tank, pond, pool, cistern, creek or irrigation line, with a strainer. Suction lift and hose length reduce flow; we include guidance in the Quick Start Guide.
7. **What are the real flow and pressure numbers?** The pump end is in the 150 GPM / 140 PSI class at 3,600 rpm. Your unit's measured wet-test numbers ship with it.
8. **How long does it run on a tank of fuel?** The iGX390 has a small onboard tank; an auxiliary tank is recommended for long runs. Our design estimate is about ten hours from a 10-gallon auxiliary tank at full throttle. This is an estimate, not a measured figure.
9. **Can I use it while I evacuate?** No. Follow evacuation orders. The remote lets you operate the pump from a distance while you are present; it is not designed for unattended operation.
10. **Will this get me an insurance discount?** We make no claim about discounts or any insurer program. Some insurers and states recognize mitigation; ask your agent.
11. **Is it UL or ETL listed?** No, and there is no UL listing for this product class. The engine carries Honda's EPA/CARB certification; the control box will have an FCC Supplier's Declaration of Conformity.
12. **Is it patented?** Patent pending: two provisional applications filed January 2026 on the automatic remote-start system. The fob-controlled v1 is not itself the subject of those filings.
13. **Why Honda?** The iGX390 has electric start, a drive-by-wire throttle the control box can command, and a nationwide dealer network for engine service and warranty.
14. **Can I retrofit my existing pump?** If it has a Honda iGX390 electric-start engine and a 12 V battery, the Remote Control Kit reward is for you. Other engines are not supported in v1.
15. **Do I need internet, Wi-Fi or a phone?** No. Nothing in v1 connects to anything.
16. **Is there a subscription?** No.
17. **Where do you ship?** Contiguous US only, by LTL freight with liftgate. Pickup in Bend, Oregon, is available.
18. **What is the warranty?** 12 months on the frame, harness, control box, remote system, valve and pump end; Honda's warranty on the engine. Optional 24-month extension add-on.
19. **Is fuel or oil shipped in the unit?** No. Units ship drained. Add oil and fuel per the Quick Start Guide.
20. **What maintenance does it need?** Honda's engine schedule (oil, filter, plug), a fob battery every year or so, and a monthly test run in fire season, which the remote makes easy.
21. **Can I get a refund?** Before parts are ordered (about three weeks after the campaign ends) yes, in full. After that, refunds are at our discretion less non-recoverable costs, and we will always tell you where your unit is in the build.
22. **Do you collect sales tax?** No. Oregon has no sales tax. Backers in other states may owe use tax.
23. **What if the campaign does not reach its goal?** Nobody is charged and nothing is built. That is Kickstarter's all-or-nothing rule.

F. Backer survey (after campaign)

Ship-to address (residential/business, liftgate access, phone for freight appointment), Bend pickup yes/no, fob quantity confirmation, safety acknowledgement checkbox (text in WARRANTY_AND_TERMS_DRAFT .md), name for Founding Backers page (opt-in), and for Kit backers the engine model and photo of the pump.

Reward Structure — Dry Lightning 3000 Kickstarter (DRAFT v1, 2026-09-17)

Status: PROPOSED. Prices, caps and delivery windows are draft decisions for Jeremy and the advisor. All numbers tie to 03_financial_model/WW_Kickstarter_Financial_Model_v1.xlsx (Inputs section C, Rewards sheet).

Shipping region for every physical reward: **contiguous United States only** (no Alaska, Hawaii, Canada or international). Reasons: freight cost on a 165 lb crate, engine emissions/registration differences, and the product-liability policy being sought is a US policy. Kickstarter's pledge maximum for US projects (\$10,000) rules out a two-pump tier.

Delivery windows assume a 2027-01-19 launch, 30-day campaign (ends 2027-02-18), payout about 2027-03-04, parts ordered the same week, 3-week engine/pump-end lead time, and founder-built assembly at roughly 4 pumps per week (Capacity sheet). Windows include a one-month buffer.

Tiers

#	Reward title (Kickstarter, ≤ 60 chars)	Price	Shipping (US)	Qty cap	Est. delivery	Contribution margin (Base)
1	Supporter — Backer Wall + Decal	\$35	\$0 (included)	none	March 2027	~\$29
2	Remote Control Kit (Honda iGX390 electric-start retrofit)	\$1,250	\$25	10	May 2027	~\$680
3	Dry Lightning 3000 — Early Bird	\$4,699	\$349	10	June 2027	~\$1,600
4	Dry Lightning 3000 — Kickstarter Price	\$4,999	\$349	15	July 2027	~\$1,875
5	Dry Lightning 3000 + Hose & Nozzle Package	\$5,599	\$349	10	July 2027	~\$2,010

Hard cap on pumps across tiers 3–5: **35 units**. Above that the founder-built plan needs contract assembly (see Manufacturing plan). The campaign can close tiers early.

Tier 1 — Supporter — Backer Wall + Decal (\$35)

Includes: name on the "Founding Backers" page at wildfirewatchdog.com (opt-in), one weatherproof Wildfire Watchdog decal, all backer updates including the build log and test videos.

Excludes: any equipment.

Ongoing costs: none.

Tier 2 — Remote Control Kit (\$1,250 + \$25 shipping, limit 10)

Includes: the same four-channel rolling-code remote system used on the DL3000, packaged as a retrofit for a pump the backer already owns: two Solidremote 202U rolling-code receivers, one TX-134 four-button fob (plus one spare fob), sealed relay enclosure with three 12V relays and manual override switches, pre-terminated harness with Deutsch DT 6-pin Remote Port, inline fuses, 2 in. 12V spring-return electric ball valve (normally closed), printed installation guide, phone/email

installation support.

Compatibility (must be stated plainly on the reward): **Honda iGX390 electric-start engines only** in v1 (the engine the prototype uses). NorthStar 420cc compatibility is planned but NOT yet bench-tested (briefing 2026-09-10 lists it as an open action), so it is not promised. Backer must have a 12V battery on the pump and be comfortable with basic 12V wiring or hire a small-engine shop.

Excludes: engine, pump, battery, hoses, installation.

Ongoing costs: fob battery (CR2032-type, ~\$2/yr).

Why it exists: lets people who already own a good pump back the project at a lower price, and it is the accessory the business plan wants to sell as a standalone SKU anyway. Capped at 10 to limit support load.

Tier 3 — Dry Lightning 3000 — Early Bird (\$4,699 + \$349 freight, limit 10)

Includes (the "DL3000 v1 base package", identical in tiers 3, 4, 5):

- Honda iGX390 electric-start engine (389 cc) with matched high-pressure pump end, on a powder-coated steel skid/frame
- Four-channel rolling-code RF remote (start / run-stop / throttle / discharge valve) with one fob in use plus three spare fobs (as shipped in the two receiver kits)
- Sealed relay enclosure with failsafe wiring (loss of signal or power = engine kill, throttle to idle, valve closed) and manual override switches so the pump runs with nothing plugged in
- 2 in. 12V spring-return electric discharge valve, float valve, 2 in. camlock discharge fitting
- 12V battery, USB power bank and solar maintainer panel
- Deutsch DT 6-pin Remote Port (documented) for future controller upgrades
- Printed Quick Start Guide, warning labels, wet-test certificate with the unit's measured flow and pressure
- 1-year limited warranty (draft terms in WARRANTY_AND_TERMS_DRAFT .md)
- Phone and email support from the builder

Excludes: fuel, suction hose and strainer, discharge hose and nozzle, sprinklers, water tank, installation, any app/internet/monitoring feature.

Ongoing costs: fuel and engine maintenance (oil, filter, spark plug) per Honda schedule; fob battery. No subscriptions.

Delivery: June 2027, contiguous US, LTL freight to a residential address with liftgate. Backer must be able to receive a 165 lb crate.

Tier 4 — Dry Lightning 3000 — Kickstarter Price (\$4,999 + \$349, limit 15)

Same package as Tier 3. Price equals the MAP proposed to Northern Tool, so a future retail partner is not undercut. Delivery July 2027.

Tier 5 — Dry Lightning 3000 + Hose & Nozzle Package (\$5,599 + \$349, limit 10)

Tier 4 package plus: 50 ft of 2 in. single-jacket discharge hose with camlock ends, adjustable fog/straight-stream nozzle, 20 ft 2 in. suction hose with foot valve and strainer, one additional spare fob. Delivery July 2027.

Note: this is the only tier that lets a backer pump water on delivery day without buying anything else except fuel and a water source.

Add-ons (Kickstarter "add-on" items, optional, PROPOSED)

Add-on	Price	Notes
Extra rolling-code fob (paired before shipping)	\$45	Only with tiers 2–5

Add-on	Price	Notes
Second 50 ft 2 in. discharge hose with camlocks	\$220	Only with tiers 3–5
Extended warranty to 2 years (parts + labor at our shop, freight excluded)	\$350	Only with tiers 3–5

What is deliberately NOT offered

- Sprinkler systems, roof sprinklers, manifolds or "complete house protection" kits. The insurer question "do you manufacture or sell sprinkler systems?" was answered No for this SKU; adding them changes the insurance class.
- Phone / app / cloud control, sensors, auto-start on smoke or heat, or monitoring. These exist as a demonstrated prototype but are not FCC-declared or insured for sale. They are described in the campaign as the next development stage, not as a reward.
- Trailer or pump-house systems (freight, install-heavy, semi-custom).
- Two-pump bundles (above the \$10,000 pledge cap).
- Stretch goals that add product scope. If the campaign overfunds, the only "stretch" is opening more units of tiers 4 and 5 up to the 35-pump cap.
- Any tier that implies installation or site service.

Reward-page wording that must appear on every pump tier

"Preparedness equipment, not a guarantee. This product does not make property fireproof, does not guarantee protection, does not replace defensible space, firefighters or evacuation orders, and is not a monitoring, alarm or fire-detection device. The remote operates the pump only while an operator is present to supervise it. Requires a water source, fuel, hoses and a 12V battery (battery included)."

Sales-tax and shipping notes

- Kickstarter does not collect sales tax. Oregon has no sales tax. Backers in other states may owe use tax; state that in the FAQ.
- Shipping is entered per reward as a flat US amount, so it is visible to backers and inside the fee base.
- Freight to a business address with a dock is cheaper; offer a \$60 refund by backer survey for dock delivery (PROPOSED).

Manufacturing and Fulfillment Plan — DL3000 Kickstarter batch (DRAFT v1, 2026-09-17)

Scope: 10–35 DL3000 units plus up to 10 Remote Control Kits, founder-built in Bend, Oregon, shipped to contiguous-US backers between April and July 2027. Labels: VERIFIED / ESTIMATE / PROPOSED / UNKNOWN.

1. Bill of materials (per DL3000) and sourcing status

#	Part	Qty	Unit cost (Base, 10 units)	Status	Sourcing status	Notes
1	Honda iGX390 electric start (Q-type, 389 cc, 12V charge coil)	1	\$1,150	ESTIMATE	UNKNOWN — no dealer quote on file; "Honda quote" is a listed closeout item	Prototype uses this engine. Retail list is ~\$1,100–\$1,300. Ask 2 Honda engine distributors for 10/20/35-unit pricing.
2	High-pressure pump end, 2 in. NPT, bronze closed impeller, 3,600 rpm	1	\$260	ESTIMATE	UNKNOWN — RFQ targets identified (IMBO, Bombas Nilo, Roarkit/Alibaba) but no quote or sample record	Prototype pump head listed at ~\$90 in the sourcing sheet; small-batch price used is higher. Sample must be wet-tested before ordering the batch.
3	Steel skid/roll-cage frame, powder coat	1	\$260	ESTIMATE	UNKNOWN — no fabricator quote	Local Bend fab shops; ask for a 10-piece and 35-piece price.
4	Solidremote KIT-1 (202U receiver + TX-134 fobs)	2	~\$95 (both)	ESTIMATE	Available (KIT-2/402U out of stock everywhere per briefing)	Price not documented in Drive; check Solidremote direct.
5	12V 30A 5-pin automotive relays with pigtail	3	\$15	ESTIMATE	Commodity	
6	2 in. 12V spring-return normally-closed electric ball valve	1	\$180	ESTIMATE	UNKNOWN — prototype uses a CR04 motorized valve (\$102, VERIFIED bought), not spring-return	Spring-return is what the failsafe design specifies; confirm supplier and price.
7	Float valve, 2 in. camlock fittings, strainer, unions	1 set	\$50	ESTIMATE	Partly bought for prototype (VERIFIED)	
8	Deutsch DT 6-pin connector kit, ATC fuse holders (5A, 10A), 16 AWG GXL wire, terminals	1 set	\$35	ESTIMATE	Commodity	

#	Part	Qty	Unit cost (Base, 10 units)	Status	Sourcing status	Notes
9	Manual override switches (1 momentary, 3 toggle), sealed ABS enclosure, glands	1 set	\$45	ESTIMATE	IP65 enclosures bought at \$15 (VERIFIED)	
10	12V battery (AGM or LiFePO4 20Ah), USB power bank, solar maintainer, cabling	1 set	\$140	ESTIMATE	Amazon list prices on file (ESTIMATE)	
11	Warning labels, Quick Start Guide print, wet-test certificate	1	\$15	ESTIMATE	In-house	
12	Assembly + wet test labor (6 h × \$40)	1	\$240	ESTIMATE	Founder + helper	
13	QC consumables (test fuel, oil)	1	\$30	ESTIMATE		
14	Warranty reserve	1	\$150	ESTIMATE		
15	Crate (2-way pallet, corner posts, strapping, corrugated)	1	~\$60 (inside freight line)	ESTIMATE	Local	
	Total per unit ex freight		\$2,665			Conservative +15% = \$3,065; modeled 20+ unit discount = \$2,487

Kickstarter-specific: no supplier has been asked for a quote yet. The RFQ drafts below are ready to send after approval. Ordering nothing before payout is the cash-minimizing path (Cash_Timing sheet).

2. Assembly and test sequence (per unit)

1. Receive and inspect engine, pump end, frame (serial numbers logged in the build sheet).
2. Mount engine and pump end to frame; torque check; fit suction/discharge fittings and float valve.
3. Build harness on the bench from the harness drawing: battery → 5A fuse → Remote Port pin 1; relay box K1 (kill), K2 (throttle), K3 (valve); starter via receiver 10A contact with a starter-isolation relay (the 2026-08-02 prototype fault was the starter cranking from battery backfeed); Receiver 2 powered from RUN line (interlock).
4. Bench-test relay logic with a test fob before installing on the pump: crank pulse, run toggle, throttle toggle, valve toggle; confirm C and D are dead when RUN is off.
5. Failsafe timing test: with engine running, remove RUN signal; record time to ignition kill, throttle to idle, valve closed (must be ≤ 2 s per design spec).
6. Manual override test with nothing plugged into the Remote Port.
7. Wet test: 20–30 minutes on a tank, record flow (calibrated flow meter) and discharge pressure at full throttle and idle; record on the unit's wet-test certificate.
8. Remote range test at 50, 100 and 150 ft line-of-sight; record.
9. Drain, dry, apply warning labels and serial plate, pair and label spare fobs, pack Quick Start Guide.

10. Photograph the finished unit (front, side, control box, serial) for the backer's delivery email.

11. Crate, strap, label; book LTL with liftgate and residential delivery; email tracking.

Time per unit: ~6 hours founder-built (ESTIMATE). Fixtures that cut this: harness jig, pre-cut wire kits, a relay-box sub-assembly built in batches of 10.

3. Capacity limits

- Founder time: ~25 h/week → about 4 pumps/week (Capacity sheet).
- 18 pumps (Base) → ~5 build weeks; 28 (Optimistic) → ~7 weeks; plus 3-week parts lead time and 1 week freight. That fits the June/July delivery windows with a month of buffer.
- Above 35 pumps: contract assembly (OMEP referral from SBDC on 2026-09-16 is the lead) or a part-time helper. The reward caps prevent this in v1.
- Space: home shop and outdoor workspace (business plan §1.1). Ten crated pumps need roughly 100 sq ft of covered storage.

4. Quality checks and documentation

- Build sheet per serial: parts lot numbers, torque checks, harness continuity, failsafe timing, wet-test flow/pressure, range test, inspector initials, photos.
- Retain build sheets for the life of the product (insurer "written QC procedure" requirement noted in the business plan).
- Warning label set: hot surfaces, CO/outdoor use only, pressurized hose, "REMOTE ENGINE CONTROL PORT — DO NOT DISCONNECT WHILE ENGINE MAY BE ARMED", "preparedness equipment, not a guarantee".

5. Packaging and shipping assumptions

- Packed 40 × 28 × 24 in, 165 lb (Northern Tool quote sheet, 2026-09-12; unit ~36 × 24 × 18 in, ~145 lb).
- Ship drained, no fuel, battery disconnected with a shipping tag; oil either drained (ship "dry") or filled with a hang tag. Batteries: AGM ships ground without hazmat paperwork; if LiFePO4 is used, ship under UN3481-compliant packaging or switch to AGM for simplicity (PROPOSED: AGM).
- Freight class 85–100; LTL residential with liftgate, from Bend OR 97702. Charged to backer: \$349 flat (ESTIMATE, cost modeled at \$380 including crate). Get two carrier quotes before launch.
- Kits: UPS Ground, ~8 lb box, \$22 cost.
- Supporter decals: first-class envelope.

6. Support workflow

- Channel: support@ or admin@wildfirewatchdog.com and 541-419-3203 (business hours); backer messages on Kickstarter answered within 2 business days.
- Delivery email includes: serial, wet-test certificate, photos, Quick Start Guide PDF, first-start video link, warranty terms.
- 30-day check-in email after delivery; 6-month reminder for oil change and fob battery.
- Warranty claim: photo/video first, phone diagnosis, parts shipped for backer-replaceable items (relays, fob, fuses, valve actuator), return-to-shop for engine/pump issues (Honda engine warranty handled through Honda dealer network).
- Log every contact in a simple sheet (date, serial, issue, fix) — feeds the QC loop and the insurer's audit.

7. Timeline (Base)

Week of	Milestone
2026-10-05	Photos, video shot list, landing page, email tool
2026-11-02	Fixtures and crimp tooling; RFQs sent (after approval); carrier quotes
2026-12-07	Kickstarter prelaunch page live; demo video edit
2027-01-19	Launch
2027-02-18	Campaign ends
2027-03-04	Payout; engines, pump ends, frames ordered; insurance bound; FCC SDoC started
2027-03-29	Parts in; batch 1 assembly
2027-04-12	Kits and supporter rewards ship
2027-05-03	Early Bird pumps wet-tested and shipped
2027-06-14	Tier 4/5 pumps ship
2027-07-15	Fulfillment complete; final backer update

8. Risks specific to fulfillment and how they are handled

- Pump-end supplier fails sample test → fallback to a US-stocked 2 in. high-pressure pump end (higher cost; covered by contingency).
- Engine price/availability → order within a week of payout; Honda distributors stock iGX390.
- Spring-return valve actuator lead time → order at payout; substitute a motorized valve with a capacitor-backed close circuit only if the failsafe test still passes.
- Freight damage → crate with corner posts; photograph before pickup; declared value on the BOL.
- Founder illness/time → build order is Early Birds first; kits can be built by a helper from the jig.

Marketing Package — Dry Lightning 3000 Kickstarter (DRAFT v1, 2026-09-17)

Everything here is unsent and unscheduled. Nothing goes out without Jeremy's approval. Dates assume launch 2027-01-19 and end 2027-02-18; shift everything if the launch moves.

Two paths are provided: **Path A (no ad spend)** uses existing relationships, the existing email list (if any), the Facebook page, local press and fire-safety organizations. **Path B (optional, separately costed)** adds a small Meta test. The financial model treats Path B as optional (\$0–\$5,000; \$1,500 in the base case).

1. 30-day prelaunch plan (Dec 20, 2026 – Jan 18, 2027)

Day	Action	Path
–30 (Dec 20)	Kickstarter prelaunch page live with cover, blurb, 3 photos, "Notify me" button. Prelaunch landing page live at wildfirewatchdog.com/kickstarter (draft in 08_preview_site/).	A
–30	Email 1 to existing contacts: Metolius customer, Camp Sherman and Coldstream leads, SBDC/SCORE advisors, Skyliner customers who own rural property (only where consent allows), friends and family.	A
–28	Facebook page post 1 (behind-the-scenes shop photo).	A
–25	Personal messages to 20 people most likely to back on day one (target: 10 verbal yeses; ~30% of Kickstarter followers convert, so day one needs a list, not luck).	A
–24	Send press release (draft below) to The Bulletin (Bend), Bend Source Weekly, Central Oregon Daily, OPB, KTVZ; media pitch to Oregon Capital Chronicle and fire-industry newsletters.	A
–21	Post 2 (the four buttons explained). Email 2.	A
–20	Reach out to Deschutes County Firewise USA coordinators, Project Wildfire (Bend), Oregon Fire Chiefs Association newsletter, local HOAs in the WUI (Sisters, La Pine, Sunriver, Black Butte) with the "for your members" note below.	A
–18	Optional Meta test: \$10–\$20/day, Central Oregon + SoCal WUI zips, objective = prelaunch page follows; measure cost per follow.	B
–14	Post 3 (failsafe video clip). Email 3. Finish demo video edit.	A
–10	Ask 3 backers-in-waiting for a short quote ("why I'm backing") for launch-day post.	A
–7	Post 4 (rewards and prices). Range test video clip.	A
–5	Second press touch: "launching next week" note to any reporter who replied.	A
–3	Email 4 (launch date and the Early Bird cap). Post 5.	A

Day	Action	Path
-1	Final page check: title/blurb counts, reward caps, shipping, FAQ, Risks, AI disclosure, Late Pledges enabled.	A
0 (Jan 19, 8 am PT)	Launch. Email 5 to the whole list. Post 6. Personal messages to the day-one list.	A

Success metric for prelaunch: ≥ 300 **Kickstarter followers** and ≥ 10 **committed pump backers** before launch. Below that, consider delaying a month rather than launching soft.

2. Campaign-period calendar (30 days)

Day	Action
1	Launch email + posts; reply to every comment within 4 hours; post first update ("we're live, here's the plan").
2	Update: day-one thank you, Early Bird count remaining.
3	Post 7: "what's in the box" flat-lay.
5	Email 6 (72-hour recap + FAQ highlights). Press follow-up with launch numbers.
7	Update: wet-test video with measured flow and pressure on a gauge.
9	Post 8: manual-override clip. Answer FAQ questions publicly in updates.
12	Live Q&A (Facebook Live or Kickstarter Live) from the shop, pump running.
14	Mid-campaign update: honest progress vs goal, what happens if we fall short.
15–20	The quiet middle: one post every other day, reply to every message, send targeted notes to fire districts and HOAs.
21	Update: supplier status (which quotes are in), no surprises.
24	Post 9: founder-to-camera, why the caps exist.
26	Email 7 ("last 72 hours").
28	Post 10: final range/failsafe clip; update with final counts.
30	Last-day email and posts (morning and 6 hours before close). Enable Late Pledges (must be on before end).
+1	Thank-you update; backer survey timeline; first supplier orders after payout.

Backer updates continue every two weeks through delivery (templates in §9).

3. Seven-email sequence (English; Spanish in §10)

Email 1 — "I'm putting the pump on Kickstarter in January" (Dec 20)

Subject: The remote-start pump is going on Kickstarter

Hi [first name], it's Jeremy at Wildfire Watchdog. For the last two years I've been building a water pump you can start, throttle and open from a key fob instead of standing next to it. The prototype works. On January 19 I'm opening a Kickstarter to build the first batch here in Bend. If you'd like first access to the ten Early Bird units, tap "Notify me" here: [prelaunch link]. No obligation. I'll send a handful of emails between now and then, and you can unsubscribe any time. Jeremy

Email 2 — "Four buttons" (Dec 29)

Subject: What the four buttons on the fob actually do

A: crank. B: run, and press again to stop. C: throttle up. D: open the discharge valve. C and D are dead unless the engine is enabled, and if the power or the signal drops, the engine kills, the throttle drops to idle and the valve closes on its own. That's relays, not software. [photo/clip] Here's the prelaunch page if you haven't followed yet: [link].

Email 3 — "The part nobody films" (Jan 5)

Subject: 1.4 seconds [replace with measured number]

I timed the failsafe this week: from losing the RUN signal to engine off, throttle at idle and valve closed. [clip] Every unit I ship gets this test and a wet test, and you get the numbers on paper. Launch is January 19. Early Birds are capped at ten.

Email 4 — "Prices, honestly" (Jan 16)

Subject: What it will cost, and why

Early Bird \$4,699 (ten units). Kickstarter price \$4,999. With the hose and nozzle package \$5,599. Freight to the lower 48 is \$349, shown separately so you can see it. A good Honda pump and a start/stop remote kit cost about \$1,500 together; here's what the rest buys: [short list: drive-by-wire throttle, powered valve, failsafe box, fire fittings, Oregon assembly, warranty, support]. Launch Tuesday 8 am Pacific: [link].

Email 5 — "We're live" (Jan 19)

Subject: It's live: Dry Lightning 3000 on Kickstarter

The campaign is open: [link]. Ten Early Birds at \$4,699. If it doesn't reach the goal, nobody is charged. Thank you for reading this far; if you know one person who lives on the fire map, forward this.

Email 6 — "72 hours in" (Jan 24)

Subject: Day 5: where we stand

[X] backers, [Y]% of the goal, [Z] Early Birds left. Most-asked questions so far: Does it start itself? No. Does it need internet? No. Where do you ship? Lower 48. Full FAQ on the page: [link].

Email 7 — "Last 72 hours" (Feb 15)

Subject: Closes Thursday

The campaign closes Thursday, February 18 at [time]. [Status]. After that, the next chance is retail pricing later in the year. [link]

4. Ten social posts (Facebook/Instagram; Spanish in §10)

1. Shop photo, harness on the bench. "Two years of nights in this shop. In January I'm putting the remote-start pump on Kickstarter. Follow the prelaunch page to hear first."
2. Fob macro. "A crank. B run/stop. C throttle. D valve. Rolling code, no app, no internet."
3. Failsafe clip. "Pull the plug while it's running. Engine off, throttle idle, valve closed. Wiring, not software."
4. Rewards card. "Early Bird \$4,699, ten units. Kickstarter price \$4,999. Lower 48 freight shown separately."
5. Wet test. "Every unit gets a wet test and you get its measured flow and pressure. No catalog numbers."
6. Launch day. "We're live. If the goal isn't met, nobody is charged."
7. Flat-lay: fobs, manual, certificate, labels. "What's in the box."
8. Manual override clip. "Left the fob in the other truck? The switches on the pump work with nothing plugged in."
9. Founder to camera. "Why I capped it at 35 pumps: because I'm the one building them."

10. Final clip, water arc. "Closes Thursday. Thank you, Central Oregon."

Rules for every post: real photos/video only; never show fire, smoke or embers; never say "only," "guaranteed," "saves lives," or "protects your home"; always include "preparedness equipment, not a guarantee" in the first comment or caption.

5. Five ad concepts (Path B, optional)

#	Concept	Hook line	Creative	Audience	Budget note
1	The pull-cord	"Who's going to pull the cord when the sky is orange?"	15-s clip: fob press from 100 ft, engine starts, water arcs	Rural homeowners 45–65, OR/WA/N. CA/CO, interests: Firewise, ranching, generators	\$10/day prelaunch test
2	Four buttons	"Start. Throttle. Valve. Stop. From your porch."	Feature panel graphic + 6-s clip	Same	\$10/day
3	Failsafe	"If the signal drops, it shuts itself down."	Stopwatch overlay clip	Engineers, off-grid, prepper-adjacent interests	\$5/day
4	No app	"Works when the cell tower doesn't."	Static image: fob + pump, text	Rural OR/CO/N. CA	\$5/day
5	Built in Bend	"One guy, one shop, first batch on Kickstarter."	Founder photo in shop	Central Oregon radius 60 mi	\$5/day

Optional plan cost: \$1,500 over 45 days (prelaunch + campaign). Stop rule: if cost per Kickstarter follow exceeds \$8 after \$200 spent, stop and rely on Path A. Not required to hit the goal.

6. Press release (draft, unsent)

FOR RELEASE [date]

Bend inventor puts remote-start wildfire water pump on Kickstarter

BEND, Ore. — Wildfire Watchdog LLC, a one-person company in Bend, will open a Kickstarter campaign on January 19 for the Dry Lightning 3000, a Honda-powered high-pressure water pump that its owner can start, throttle and open from a handheld key fob rather than standing beside the engine.

Founder Jeremy Coon built the control system in his Bend shop after installing a fixed three-building pump and sprinkler system on the Metolius River in 2026. "Every pump I could buy assumed someone was standing next to it when it mattered," Coon said. "I wanted one I could run from the truck or the end of the driveway, and that would shut itself down safely if the signal or the power dropped."

The pump uses a rolling-code four-button remote wired through relays so that losing power or signal kills the engine, returns the throttle to idle and closes the discharge valve. It has no app, internet connection or subscription. Two provisional patent applications on the automatic version of the system were filed in January 2026.

The campaign seeks \$60,000 to build a first batch of ten to thirty-five pumps in Bend, with delivery to the contiguous United States planned for spring and summer 2027. Kickstarter is all-or-nothing: if the goal is not met, no backer is charged.

Coon is careful about what the product is not. "It doesn't detect fire, it doesn't start itself, and it won't make a house fireproof. If you're told to evacuate, evacuate. What it does is let you put water where you need it without walking into the smoke to do it."

Campaign page: [link]. Media contact: Jeremy Coon, admin@wildfirewatchdog.com, 541-419-3203. Photos and video of the prototype available on request.

7. Media pitch (email to a reporter, unsent)

Subject: Bend inventor's remote-start wildfire pump, Kickstarter Jan 19

Hi [name], I'm Jeremy Coon in Bend. I build water-pump control systems; this winter I'm putting a Honda-powered pump you start and run from a key fob on Kickstarter. The angle that might interest your readers: the failsafe wiring (lose signal, it shuts down), the insurance climate in Deschutes County, and a one-person shop trying to build 35 units without borrowing against inventory. I can demo it running for you or send raw video. Launch is January 19. Thanks for reading. Jeremy, 541-419-3203

8. "For your members" note (Firewise, HOAs, fire districts, unsent)

Subject: A remote-start pump from a Bend builder, for your members

Hi [name], I'm a Bend resident building a Honda-powered water pump that can be started, throttled and opened from a key fob, so a homeowner doesn't have to stand next to a running pump to wet down a roof or defensible space. It's going on Kickstarter January 19. I'm not asking for an endorsement; I'd like to send you the campaign link and a one-page fact sheet in case any of your members are shopping for pumps this winter, and I'm happy to demo it at a meeting. It is preparedness equipment, not a guarantee, and it doesn't replace defensible space or evacuation. Jeremy Coon, Wildfire Watchdog LLC, 541-419-3203

9. Backer update and support templates

Update: launch day. "We're live. Here's exactly what happens next: [timeline]. I'll post every two weeks, more if something changes. Questions go in the comments and I answer all of them."

Update: milestone. "[X]% funded, [N] pumps. Early Birds left: [n]. This week: [wet test numbers / supplier quote / photo]."

Update: supplier status (day 21). "Quotes in: engines [status], pump ends [status], frames [status], valves [status]. Nothing ordered until funds arrive; that's deliberate so no one's money is at risk before the goal."

Update: funded, next steps. "Funded. Payout expected [date]. Orders go in that week. Backer survey goes out [date]; please answer the freight questions carefully, it decides how your crate is delivered."

Update: delay (if needed). "[Part] is [n] weeks late. New estimate for tier [X]: [month]. What I'm doing about it: [action]. If you'd rather cancel, reply and I'll refund [terms]."

Update: shipping. "Serial [n] is crated. Tracking: [link]. Your wet-test certificate and photos are attached. Call me when it arrives and we'll do the first start together."

Support reply: not starting. "Let's check three things: battery voltage at the port (should read above 12.4 V), the RUN toggle position, and whether the fob LED lights when pressed. Send me a 30-second video and I'll call you."

Support reply: warranty claim. "Sorry about that. Send serial, photos and a short description; I'll ship the replacement [part] within two business days or arrange return to the shop, per the warranty terms."

10. Spanish versions of customer-facing messages

Correo 1: Hola [nombre], soy Jeremy de Wildfire Watchdog. Durante los últimos dos años he construido una bomba de agua que se arranca, acelera y abre desde un control remoto en lugar de pararse junto a ella. El prototipo funciona. El 19 de enero abro una campaña en Kickstarter para fabricar el primer lote aquí en Bend. Si quieres acceso prioritario a las diez unidades Early Bird, toca "Avísame" aquí: [enlace]. Sin compromiso.

Correo 5 (lanzamiento): Ya está en vivo: Dry Lightning 3000 en Kickstarter [enlace]. Diez unidades Early Bird a \$4,699. Si no se alcanza la meta, no se cobra a nadie. Si conoces a una persona que vive en el mapa de incendios, reenvía este

correo.

Correo 7 (últimas 72 horas): La campaña cierra el jueves 18 de febrero. [Estado]. Después de eso, la siguiente oportunidad es a precio de venta al público más adelante en el año.

Publicaciones sociales:

1. "Dos años de noches en este taller. En enero pongo la bomba de arranque remoto en Kickstarter."
2. "A arranque. B marcha/parada. C acelerador. D válvula. Código rodante, sin app, sin internet."
3. "Desconecta mientras funciona: motor apagado, acelerador en ralentí, válvula cerrada. Cableado, no software."
4. "Early Bird \$4,699, diez unidades. Precio Kickstarter \$4,999. Flete a los 48 estados por separado."
5. "Cada unidad pasa una prueba con agua y recibes su caudal y presión medidos."
6. "Ya estamos en vivo. Si no se alcanza la meta, no se cobra a nadie."
7. "Qué viene en la caja."
8. "¿Dejaste el control en la otra camioneta? Los interruptores de la bomba funcionan sin nada conectado."
9. "Por qué lo limité a 35 bombas: porque yo soy quien las fabrica."
10. "Cierra el jueves. Gracias, Oregón Central."

Aviso en cada publicación: "Equipo de preparación, no una garantía."

Actualización a patrocinadores (envío): "La unidad con serie [n] está embalada. Rastreo: [enlace]. Adjunto su certificado de prueba con agua y fotos. Llámeme cuando llegue y hacemos el primer arranque juntos."

Respuesta de soporte (no arranca): "Revisemos tres cosas: el voltaje de la batería en el puerto (debe leer más de 12.4 V), la posición del interruptor RUN y si el LED del control se enciende al presionar. Envíeme un video de 30 segundos y le llamo."

Garantía (resumen): 12 meses en bastidor, arnés, caja de control, sistema remoto, válvula y cuerpo de bomba; el motor Honda tiene la garantía de Honda a través de sus distribuidores. Envíos solo a los 48 estados contiguos.

11. Existing relationships to use (Path A)

- Metolius River customer (completed install, May 2026): ask for a short quote and permission to name the site.
- Camp Sherman and Coldstream BC leads (proposals delivered 2026): send Email 1 personally; Coldstream cannot receive a pump (US-only) but can share.
- SBDC (COCC) and SCORE advisors: ask for a share to their networks and a "local business launches" mention.
- Northern Tool contacts: do NOT reference the Kickstarter as a Northern Tool product; do inform them as a courtesy before launch and keep pricing at or above the proposed MAP.
- Skyliner Buildings customer base: only contacts who opted in to marketing; keep the businesses separate in the message (a personal note from Jeremy, not a Skyliner mailing).

Campaign Video — Script, Storyboard, Shot List, Captions (DRAFT v1, 2026-09-17)

Target length: 2:30. Real footage of the actual DL3000 prototype only. No renders, no stock fire footage presented as our own, no simulated flames. Filmed by Jeremy on a phone with a gimbal or tripod; edit in any basic editor. Spanish caption track included at the end.

Status of footage

Existing raw footage in Drive (not transferable through this session; owner must copy to the campaign folder):

- Wildfire Watchdog Automatic Remote Firefighting Pump.mp4 (2026-09-03, 65 MB, Drive id 1J5DdP8cs4Z1xjDjs6NcbW5YKAv_Od7lY) — demo of local toggle and phone/dashboard start (prototype version)
- drylightningpt1.mp4 (2026-08-30, 160 MB, id 1TvFvU5bcVXb8DO4tE-i0G9KFiNZA14qq)
- PXL_20260817_025402075.mp4 (2026-08-17, 135 MB, id 12MlbRhJh9WbhHNu4SolxzKVobMIFu3RS) — shot the same night as the product-page photos
- sprinklerspt1.mp4 / sprinklerspt2.mp4 (2026-08-30) — sprinkler footage, usable only as clearly labeled "customer sprinkler lines fed by a pump", not as DL3000 v1 features
- YouTube Short BqMepkZrpSg (sent to Northern Tool)

Preview gap: none of these show the four-button fob sequence on the production receivers, the failsafe stop, or measured flow/pressure. Those are the required new shots below. No reviewable edit could be produced in this session (footage not accessible from the sandbox and the phone/dashboard demo shows the non-v1 control path).

Script (voice-over, Jeremy, plain and unhurried)

Time	Shot	Voice-over / on-screen text
0:00–0:06	Wide, dawn light, Central Oregon juniper and a rural home. Jeremy walks into frame carrying nothing but a key fob.	VO: "This is Bend, Oregon. Every summer we watch the fire maps."
0:06–0:14	Medium: the DL3000 on its skid beside a water tank, hoses connected, discharge line laid out toward the house. Jeremy stands 100 feet away.	VO: "Every gas pump I could buy assumed somebody was standing next to it when it mattered." Text: *Dry Lightning 3000*
0:14–0:24	Close on the fob in hand. Press A (crank), then B (run). Cut to engine cranking and catching. Real audio.	VO: "So I built one you don't have to stand next to." Text: *A: Crank · B: Run*
0:24–0:34	Press C. Engine note rises to full throttle. Then press D. Cut to the 2 in. valve actuator turning; water hits the nozzle and arcs over the roofline.	VO: "Start it. Bring it to full throttle. Open the valve. From the truck, the porch, or the end of the driveway." Text: *C: Throttle · D: Valve*
0:34–0:48	Slow pan along the skid: Honda iGX390 badge, pump end, control box, Deutsch port, battery and solar panel.	VO: "It's a commercial Honda iGX390 engine and a high-pressure pump end on a steel skid, with a control box I designed and wire myself here in Bend."
0:48–1:02	Two-shot: Jeremy at the fob; second camera on the control box. He presses B (stop). Engine dies, throttle lever drops, valve closes. Overlay a stopwatch reading the measured time.	VO: "The part that matters most is what happens when things go wrong. Press stop, lose power, or lose the signal, and the engine kills, the throttle drops to idle and the valve closes on its own. That's not software. It's how the relays are wired." Text: *Failsafe: measured [X.X] s*

Time	Shot	Voice-over / on-screen text
1:02–1:12	Close on manual switches on the pump. Jeremy unplugs the Remote Port, flips the toggles, engine starts.	VO: "And if the remote is in the other truck, the switches on the pump still work with nothing plugged in."
1:12–1:26	Jeremy in the shop at the bench with harnesses, a relay box open, the fob receivers visible. Real build footage.	VO: "I've spent two years on this: wireless sprinkler controllers, a three-building system I installed on the Metolius River, firmware, and a lot of nights in this shop. Two provisional patent applications on the automatic version are on file."
1:26–1:40	Insert: phone screen with the prototype dashboard starting the pump (from the existing 2026-09-03 demo), clearly labeled.	VO: "The prototype can also be started from my phone. That's not in this first batch, and I'll tell you exactly why on the campaign page. Every unit ships with the port for it." Text: *Prototype only — not included in v1 rewards*
1:40–1:56	Flow meter and pressure gauge in frame while the pump runs; Jeremy reads the numbers aloud. Then the wet-test certificate being signed.	VO: "Every pump gets a wet test before it's crated, and you get its measured flow and pressure on paper, not a catalog number."
1:56–2:10	Crate being strapped; pallet on a liftgate. Then the reward cards on screen.	VO: "This campaign builds the first batch: ten to thirty-five pumps, built and tested here, shipped anywhere in the lower 48." Text: *Early Bird \$4,699 · Kickstarter \$4,999 · + Hose & Nozzle \$5,599 · Remote Control Kit \$1,250*
2:10–2:22	Jeremy to camera, pump idling behind him.	VO: "It's not a fire-detection system and it won't make your place fireproof. If they tell you to leave, leave. What it does is let you put water where you need it without walking into the smoke to do it."
2:22–2:30	Fob press, engine starts, water arcs. Logo, URL.	Text: *Dry Lightning 3000 — Wildfire Watchdog, Bend, Oregon* · *Preparedness equipment, not a guarantee.*

Storyboard notes

- Two cameras where possible: one on Jeremy and the fob, one on the machine, so the cause-and-effect of each button is undeniable. Show the fob and the machine in the same frame at least once (wide shot at 0:14).
- No music over the engine start; the sound is the proof.
- On-screen text stays under eight words per card.
- Do not show customer properties without a release; the Metolius install may be referenced by name only if the customer agrees, otherwise say "a three-building system in Central Oregon".

Shot list (new footage required)

1. Wide: pump + tank + hose + Jeremy at 100 ft, fob visible (16:9, tripod).
2. Fob close-up: A, B, C, D presses, one at a time, with pauses (macro, tripod).
3. Engine crank and catch, close (real audio, second camera).
4. Throttle lever moving idle → full on C (close).
5. Valve actuator turning and water discharge starting on D (close, then wide).
6. Water arc over a roofline or onto defensible space (wide, backlit if possible).
7. Stop on B: engine dies, throttle drops, valve closes; stopwatch overlay for failsafe timing (two cameras).

8. Signal-loss failsafe: pull the Remote Port plug while running; same three things happen.
9. Manual overrides: start and stop from the pump switches.
10. Beauty pans of the skid: Honda badge, pump end, control box label, Deutsch port, battery, solar panel.
11. Flow meter and pressure gauge readings during the wet test (close, legible).
12. Range test: fob press at measured 50 / 100 / 150 ft with a tape or rangefinder in frame.
13. Shop b-roll: harness building, relay box, receivers, labeling, crimping.
14. Crating: pallet, corner posts, strapping, liftgate.
15. Jeremy to camera, two takes, clean background.
16. What's-in-the-box flat-lay: fobs, manual, certificate, labels.

Not to be filmed or staged: fire, embers, smoke, or anyone "protecting a home during a fire."

Captions (English)

See script column; captions match the voice-over verbatim.

Subtítulos (Español)

0:00 "Esto es Bend, Oregón. Cada verano miramos los mapas de incendios."

0:06 "Cada bomba de gasolina que podía comprar suponía que alguien estaría parado junto a ella cuando importara."

0:14 "Así que construí una junto a la que no tienes que estar."

0:24 "Arráncala. Llévala a máxima aceleración. Abre la válvula. Desde la camioneta, el porche o el final del camino."

0:34 "Es un motor comercial Honda iGX390 y una bomba de alta presión sobre un bastidor de acero, con una caja de control que diseño y cableo yo mismo aquí en Bend."

0:48 "Lo más importante es lo que pasa cuando algo falla. Pulsa parar, pierde la energía o pierde la señal, y el motor se apaga, el acelerador vuelve a ralentí y la válvula se cierra sola. No es software. Es cómo están cableados los relés."

1:02 "Y si el control quedó en la otra camioneta, los interruptores de la bomba funcionan sin nada conectado."

1:12 "Llevo dos años en esto: controladores inalámbricos de aspersores, un sistema de tres edificios que instalé en el río Metolius, firmware y muchas noches en este taller. Hay dos solicitudes provisionales de patente sobre la versión automática."

1:26 "El prototipo también se puede arrancar desde mi teléfono. Eso no va en este primer lote, y en la página explico exactamente por qué. Cada unidad sale con el puerto para hacerlo."

1:40 "Cada bomba pasa una prueba con agua antes de embalsarse, y recibes su caudal y presión medidos en papel, no un número de catálogo."

1:56 "Esta campaña construye el primer lote: de diez a treinta y cinco bombas, fabricadas y probadas aquí, enviadas a cualquier lugar de los 48 estados contiguos."

2:10 "No es un sistema de detección de incendios y no hará tu propiedad a prueba de fuego. Si te dicen que evacúes, evacúa. Lo que hace es dejarte poner agua donde la necesitas sin caminar hacia el humo para hacerlo."

2:22 "Dry Lightning 3000 — Wildfire Watchdog, Bend, Oregón. Equipo de preparación, no una garantía."

Source and Assumption Register (2026-09-17)

Rule used: the most recent dated primary record wins; older plans and AI-drafted material are used only when nothing newer exists. Detailed per-topic source tables live in the four research files; this is the master list of the records the campaign relies on.

A. Primary records used for campaign decisions

#	Record	Date	Link	Facts it supports	Status
1	RF_Remote_Control_DL3000_Project_Briefing.md	2026-09-10	https://drive.google.com/file/d/1PHYC9ZoPC3VXtSd3Yvx5E-y2XAcqtcvG/view	v1 = RF fob (Solidremote TX-134 + 2× 202U), 4 channels, Remote Port pinout, relay failsafe, insurance scope wording, FCC SDoC path, patent not covering fob, NTE sequencing, competitor remote-start kits	VERIFIED (current design intent)
2	DL3000_ProductPage_Divi_v2_insurance_clean	2026-09-11	https://drive.google.com/file/d/1gtG1cPmpw3QBWe4be3PMXVWjvS9CTwzr/view	Public feature list, \$5,500 target price, "specifications preliminary", standard disclaimer, hero photo URLs	VERIFIED (published copy)
3	DL3000_Quick_Start_Guide_v1	2026-09-12	https://drive.google.com/file/d/1DAi_Jpzp3yorzZ_CXT1l1tvEI40nCbW_/view	Operating/safety language, disclaimer	VERIFIED
4	WW_Plan_Negocios_2027_ES.pdf (business plan v1, Spanish)	2026-09-15	https://drive.google.com/file/d/1N28BwtNlifDaLMnSgy0iSeMgo3OGM4Tj/view	Cost table 50/150/300, patent numbers and dates, Kickstarter as 10–20-unit presale, insurance deferral to spring 2027, advisor guidance, homework list, e420 engine option	ESTIMATE figures; VERIFIED for decisions/dates
5	Wildfire Watch Dog LLC – GL Quote (Kinsale)	2026-09-01	https://drive.google.com/file/d/1Hs6Su-k2r5eT3pOvOqm6Ws8euF7HV_ek/view	\$4,597.91 premium, not bound, classification wording	VERIFIED
6	Northern_Tool_Current_Status	2026-08-29	https://drive.google.com/file/d/1QPfRCTbvHMTyZNM2F9EEeFEBfpKKPxJ9/view	NTE status = interest, not PO; demo video contents	VERIFIED
7	Northern_Tool_Line_Sheet_v3	2026-08-25	https://drive.google.com/file/d/1BZMCltPCpNs4IBxEDNPsggCvBKAuRKKT/view	DL3000 name, MSRP \$5,500, ~\$2,000 COGS claim, 150 GPM/140 PSI class, FCC module IDs	ESTIMATE (COGS), CLAIMED (specs)
8	NT Print/Sign Packet (RF)	2026-09-12	https://drive.google.com/file/d/1IQa1CPAeBx9jOKJnQ0PNvIR3CfltxvI9/view	NTE cost \$3,299 / MAP \$4,999 / sell \$5,499 proposal; packed 40×28×24 in, 165 lb	VERIFIED (proposal), not accepted terms

#	Record	Date	Link	Facts it supports	Status
9	FINAL_Complete_U SPTO_Patent_40_Claims	2025-12-20 (filed 2026-01-11)	https://drive.google.com/file/d/13F6PeWM_QxRus33k2kux5SmWz75W8MDU/view	What the provisional covers	VERIFIED
10	Finall Wildfire Watchdog Alibaba Sourcing sheet	2026-07-05	https://docs.google.com/spreadsheets/d/1lnQzWSayg7xJDFswYd_dHXykwBwKbU-bYS8GHiwUfU	Prototype part prices marked bought; iGX390 \$1,150 estimate	VERIFIED (bought marks) / ESTIMATE
11	Dry_Thunder_3000 README + firmware	2026-08-08	https://drive.google.com/file/d/1_OCd1OZN1VbmU80WnejSIF7zIJUTPcMs/view	ESP-NOW receiver functions (starter, unground, throttle, water valve, drain valve) — prototype control path	VERIFIED (code exists)
12	iGX390_Remote_Start_System (README v2, wire map, firmware v3)	2026-08-05..07	folder https://drive.google.com/drive/folders/1qQmsNOjUAZioxXg9p2Ar-9gFn_k7c-P5	Prototype wiring and pending tests	VERIFIED (code/docs exist)
13	Demo videos	2026-08-17 / 08-30 / 09-03	ids 12MlbRhJh9WbhHNu4SolxzKVobMIFu3RS, 1TvFvU5bcVXb8DO4tE-i0G9KFiNZ A14qg, 1J5DdP8cs4Z1xjDjs6NcbW5YKA v_Od7IY	Prototype running; phone/dashboard and toggle start (not fob)	VERIFIED footage exists; not viewable in session
14	Camp_Tamarack_Status	2026-08-10	https://drive.google.com/file/d/1TbHbLc4ho6xQ_IN75i5kkCMdEkMHIN5q/view	Customer install design (not DL3000 unit)	VERIFIED
15	Business Plan (2024) and pitch	2024-08	docs 1FPt9gEel2E6uVpCE5ngovj321tlaXBDRA7BGEqys9zc, 1YH047AzHCxIE7LoDR6ZEvJ9eVQQcoCOYJUC_HaMp9yk	Origin (LoRaWAN sprinkler concept); self-described background	SUPERSEDED; bio claim needs confirmation
16	Gmail: SBDC advisor thread	2026-09-01..17	thread 1a05a414cfe74bb1 (sensorinstaller@gmail.com)	"\$11,000/yr insurance"; advisor homework; OMEP referral	VERIFIED
17	Gmail: SCORE mentor thread	2026-08-31..09-02	thread 1a059354348cf3ad	Insurance difficulty for "fire suppression"	VERIFIED
18	Kickstarter rules/fees (via search extracts; direct fetch blocked)	accessed 2026-09-17	https://www.kickstarter.com/rules ; https://www.kickstarter.com/help/fees	5% + 3% + \$0.20; prototype rule; prohibited claims; \$10k cap; 60/135-char limits	VERIFIED via extracts; re-check in editor

B. Working assumptions (ESTIMATE / PROPOSED) with basis and range

See 03_financial_model Inputs sheet columns C–F: every number carries status, basis, low and high. Headline ones: engine \$1,150 (1,050–1,300), pump end \$260 (130–350), frame \$260 (200–350), remote system \$190 (140–240), valve \$230 (180–300), labor 6 h at \$40, freight \$380 cost / \$349 charged (250–450), dropped pledges 3% (1–5%), insurance \$10,598 (4,598–10,598), FCC \$2,500 (1,000–5,000), 8% modeled volume discount at 20+ units.

C. Conflicts recorded (and the conservative choice made)

Topic	Conflict	Choice
Engine	NTE packets say Honda iGX390; plan 9/15 says NorthStar e420 base	Honda (prototype engine) for this campaign
COGS	~\$2,000 "confirmed" (8/25) vs \$1,700 (9/15, e420) vs \$1,530 (RCR plan)	Built bottom-up at 10-unit pricing: \$2,665 base
Kinsale premium	\$4,598 (quote 9/1) vs ~\$6,885 (briefing 9/10)	\$4,598 documented; base model uses StarStone \$10,598 (NTE-required limits)
Insurance scope	Kinsale "installation contractor" vs required "no app/no monitoring pump" description	Copy stays inside the narrow description; flag correction of the application
Control system	ESP-NOW/dashboard (8/31 packet, demo video) vs RF fob (9/10, 9/12)	RF fob v1; phone = prototype/future
Ports	3"/2.5" (plan) vs 2" camlock (line sheet, page)	2 in.
Naming	Dry Thunder (firmware) vs Dry Lightning (all commercial docs)	Dry Lightning 3000
Range/runtime/GPM/PSI	Spec-sheet figures, none measured	"specified", "estimate", per-unit certificate
UL/ETL page in NTE packet	pulled (briefing) vs present (9/12 packet)	Not campaign-relevant; noted for NTE track

D. Evidence gaps (owner or supplier action needed)

1. No dealer/supplier quotes for engine, pump end, frame, valve, receivers, freight, FCC lab.
2. No measured flow, pressure, range or failsafe timing on the DL3000.
3. No footage of the fob-driven start/throttle/valve/stop on the real unit.
4. Hero photos exist only on the website; originals not in Drive.
5. Founder biography facts (firefighting/irrigation background) unconfirmed.
6. Business mailbox (admin@thewildfirewatchdog@) not accessible; insurer/NTE emails not read directly.
7. KVM 2 not accessible; nothing deployed there.